

nSDC/1/2017-KSITM

17/05/2018

QUOTATION NOTICE

Kerala State IT Mission inviting sealed quotations from different vendors for the shifting and installation of 82.5 KVA Diesel Generator set at Network Operating Centre, Kinfra, Kozhikode. The date of submission of sealed quotation to the Director, Kerala State IT Mission has been extended up to 24/05/2018 and the same will be opened at 03.30 pm on the same date at Kerala State IT Mission.

Work Details

Sl.No	Description	Unit	Qty
1	Foundation and plinth work of DG SET	LS	
2	Generator shifting & erection 30 metre distance from existing Location	LS	
3	Plate earth stations Supply and labour charges for Providing efficient plate earthing arrangements as per IS 3043 using 1200X1200X12mm CI plate electrode,	Nos	4
3(a)	Pipe earthing	UR	0
4	Cable termination and dismantling including excavation of cable trench.	LS	
5	Roofing of D G set using Existing Materials	LS	
6	Supply and Fixing Exhaust pipe of DG Set	Metre	25
7	25X3 MM copper strip For Supply and labour charges for Laying in ground /clamping on tray/wall & giving terminations with necessary cu sockets, brass nuts & bolts for the following copper/strip wires for effective earthing of earth pits, panels, generator.	Metre	70

*Final payment will be made based on actual quantity/measurements of materials/works and will be released upon successful Acceptance test

Director